

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	20.000 EA				
0030	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	302	302SD20-0014 6" PIPE 6" PVC	180.000 LF				
0050	302	302SD20-0025 15" CONC. PIPE	649.000 LF				
0060	302	302SD20-0039 24" CONC. PIPE	340.000 LF				
0070	302	302SD20-0049 30" CONC. PIPE	44.000 LF				
0080	302	302SD20-0199 15" END SECTION ES-1	3.000 EA				
0090	302	302SD20-0237 DROP INLET DI-1	2.000 EA				
0100	302	302SD20-0239 DROP INLET DI-2A	4.000 EA				
0110	302	302SD20-0309 DROP INLET DI-3A	1.000 EA				
0120	302	302SD20-0314 DROP INLET DI-3B,L=10'	8.000 EA				
0130	302	302SD20-0315 DROP INLET DI-3B,L=12'	1.000 EA				
0140	302	302SD20-0662 MANHOLE MH-1 OR 2	7.000 LF				

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0663 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0160	303	303SD20-0001 REGULAR EXCAVATION	453.000 CY	_____	_____	_____	_____
0170	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0180	303	303SD20-0029 SILTATION CONTROL EXCAVATION	334.000 CY	_____	_____	_____	_____
0190	303	303SD20-0030 INLET PROTECTION TYPE A	5.000 EA	_____	_____	_____	_____
0200	303	303SD20-0031 INLET PROTECTION TYPE B	19.000 EA	_____	_____	_____	_____
0210	303	303SD20-0033 TEMP. SILT FENCE TYPE B	531.000 LF	_____	_____	_____	_____
0220	303	303SD20-0034 TEMP. SILT FENCE TYPE A	398.000 LF	_____	_____	_____	_____
0230	305	305SD20-0001 BORROW EXCAVATION	520.000 CY	_____	_____	_____	_____
0240	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	1,189.000 TON	_____	_____	_____	_____
0250	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	113.000 TON	_____	_____	_____	_____
0260	315	315SD20-0008 ASPHALT CONCRETE TY. SM- 9.5D CONST	808.000 TON	_____	_____	_____	_____
0270	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	541.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE FULL DEPTH	2,926.000 LF	_____	_____	_____	_____
0290	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	10.300 TON	_____	_____	_____	_____
0300	502	502SD20-0011 CURB, STD. CG-2	372.000 LF	_____	_____	_____	_____
0310	502	502SD20-0012 CURB, RADIAL CG-2	9.000 LF	_____	_____	_____	_____
0320	502	502SD20-0014 CURB, STD. CG-3	515.000 LF	_____	_____	_____	_____
0330	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	1,438.000 LF	_____	_____	_____	_____
0340	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	206.000 LF	_____	_____	_____	_____
0350	502	502SD20-0029 ENTRANCE GUTTER CG-9D	32.000 SY	_____	_____	_____	_____
0360	502	502SD20-0031 ENTRANCE GUTTER CG-13	343.000 SY	_____	_____	_____	_____
0370	502	502SX20-0010 SAW CUT H.C.C. ITEMS SIDEWALK	156.000 LF	_____	_____	_____	_____
0380	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	45.000 SY	_____	_____	_____	_____
0390	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	1,215.000 SY	_____	_____	_____	_____
0400	504	504SD20-0004 HYDR. CEMENT CONC. SIDEWALK 7"	56.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	504	504SD20-0014 HANDRAIL HR-1 TYPE II	5.000 LF	_____	_____	_____	_____
0420	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	525.000 LF	_____	_____	_____	_____
0430	508	508SD20-0001 OBSCURING ROADWAY	8.600 UNIT	_____	_____	_____	_____
0440	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,691.000 SY	_____	_____	_____	_____
0450	510	510SD20-0038 ADJUST EXIST. VALVE & BOX	3.000 EA	_____	_____	_____	_____
0460	510	510SD20-0046 ADJUST EXIST. WATER METER & BOX	4.000 EA	_____	_____	_____	_____
0470	510	510SD20-0050 ADJUST EXIST FRAME & COVER	2.000 EA	_____	_____	_____	_____
0480	ATTD	510SX20-0001 REMOVE SIDEWALK AND ENTRANCE	215.000 SY	_____	_____	_____	_____
0490	510	510SX20-0046 ADJUST EXIST. ADJUST EXISTING SANITARY SEWER CLEAN OUT	1.000 EA	_____	_____	_____	_____
0500	511	511SD20-0001 ALLAYING DUST	45.000 HR	_____	_____	_____	_____
0510	512	512SD20-0012 TYPE 3 BARRICADE 4'	3.000 EA	_____	_____	_____	_____
0520	512	512SD20-0014 TEMPORARY SIGN	497.000 SF	_____	_____	_____	_____
0530	512	512SD20-0018 PEDESTRIAN BARRICADE DEVICE	96.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	29,348.000 DAY	_____	_____	_____	_____
0550	512	512SD20-0027 FLAGGER SERVICE	280.000 HR	_____	_____	_____	_____
0560	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	1,567.000 LF	_____	_____	_____	_____
0570	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	35.000 EA	_____	_____	_____	_____
0580	512	512SD20-0045 TEMP. PAVE. MARKER 2 WAY	35.000 EA	_____	_____	_____	_____
0590	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	3,396.000 LF	_____	_____	_____	_____
0600	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	2,532.000 LF	_____	_____	_____	_____
0610	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	1,022.000 LF	_____	_____	_____	_____
0620	ATTD	512SX20-0030 WORK AREA TEMPORARY AUDIBLE INFORMATION DEVICE	1,830.000 DAY	_____	_____	_____	_____
0630	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0640	514	514SD20-0002 FIELD OFFICE TY.II	21.000 MO	_____	_____	_____	_____
0650	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	5,587.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0670	520	520SD20-0003 1" WATER SERVICE LINE	636.000 LF				
0680	520	520SD20-0006 2" WATER SERVICE LINE	64.000 LF				
0690	520	520SD20-0016 8" DI WATER MAIN	243.000 LF				
0700	520	520SD20-0074 8" OFFSET EXIST. PIPE	114.000 LF				
0710	520	520SD20-0167 5/8" WATER METER BOX & YOKE	6.000 EA				
0720	520	520SD20-0168 1" WATER METER BOX & YOKE	1.000 EA				
0730	520	520SX20-0002 WATER FACILITIES 8" GATE VALVE AND MANHOLE	1.000 EA				
0740	602	602SD20-0006 TOPSOIL CLASS B 3"	81.000 CY				
0750	603	603SD20-0002 TEMPORARY SEED	41.000 LB				
0760	603	603SD20-0003 REGULAR SEED	54.000 LB				
0770	603	603SD20-0004 OVERSEEDING	43.000 LB				
0780	603	603SD20-0005 LEGUME SEED	3.000 LB				
0790	603	603SD20-0006 LEGUME OVERSEEDING	2.000 LB				

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,210.000 SY	_____	_____	_____	_____
0810	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	1,984.000 SY	_____	_____	_____	_____
0820	603	603SD20-0014 FERTILIZER NITROGEN - N	24.000 LB	_____	_____	_____	_____
0830	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	18.000 LB	_____	_____	_____	_____
0840	603	603SD20-0016 FERTILIZER POTASSIUM - K	18.000 LB	_____	_____	_____	_____
0850	603	603SD20-0017 LIME	1.520 TON	_____	_____	_____	_____
0860	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
0870	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	1.000 EA	_____	_____	_____	_____
0880	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	69.000 LF	_____	_____	_____	_____
0890	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	135.000 LF	_____	_____	_____	_____
0900	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	7.000 EA	_____	_____	_____	_____
0910	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	13.000 EA	_____	_____	_____	_____
0920	700	700SD20-0149 CONC. FOUND. LF-1, TY. A	16.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119472C01

Oversight/State Project No.: 0149-149-257, C501

Order No.: B24

Federal Project No.: STP-5128(579)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	700	700SD20-0178 JUNCTION BOX JB-S2	16.000 EA	_____	_____	_____	_____
0940	700	700SD20-0194 CONDUIT PVC 2"	1,620.000 LF	_____	_____	_____	_____
0950	700	700SD20-0197 TRENCH EXCAVATION ECI-1	1,620.000 LF	_____	_____	_____	_____
0960	701	701SD20-0001 SIGN PANEL	115.000 SF	_____	_____	_____	_____
0970	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	2,843.000 LF	_____	_____	_____	_____
0980	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	3,296.000 LF	_____	_____	_____	_____
0990	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	372.000 LF	_____	_____	_____	_____
1000	704	704SX20-0002 PAVEMENT MARKING PAVEMENT SYMBOL MARKING (BIKE 40" X 72") TY B CL II	9.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____