

Schedule of Items

Proposal ID: CM427PMB130210 Oversight/State Project No.: PM4B-964-27F, P401

Order No.: 412

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	1,627.540 TON	_____	_____	_____	_____
0020	307	307SD20-0001 HYDRAULIC CEMENT	181.000 TON	_____	_____	_____	_____
0030	310	310SD20-0001 TACK COAT	31,932.000 GAL	_____	_____	_____	_____
0040	315	315SD20-0036 ASPH. CONC. TY. SM-12.5E MAINT	1,273.040 TON	_____	_____	_____	_____
0050	315	315SD20-0043 ASPH. CONC. TY. IM-19.0D MAINT	722.770 TON	_____	_____	_____	_____
0060	315	315SD20-0052 RUMBLE STRIP SINUSOIDAL ASPHALT	65,534.000 LF	_____	_____	_____	_____
0070	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	21,119.000 LF	_____	_____	_____	_____
0080	315	315SP20-0049 ASPH. CONC. BMD P+VO SM- 9.5D	8,720.560 TON	_____	_____	_____	_____
0090	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	21,531.480 TON	_____	_____	_____	_____
0100	ATTD	315SX20-0013 FULL DEPTH RECLAMATION FULL DEPTH RECLAMATION 10"	6,570.000 SY	_____	_____	_____	_____
0110	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) BM-25.0	793.760 TON	_____	_____	_____	_____
0120	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0D	2,397.290 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM427PMB130210 Oversight/State Project No.: PM4B-964-27F, P401

Order No.: 412

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	512SD20-0027 FLAGGER SERVICE	2,435.000 HR	_____	_____	_____	_____
0140	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	584,778.000 LF	_____	_____	_____	_____
0150	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	195.000 LF	_____	_____	_____	_____
0160	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM		_____	_____
0170	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	985.600 SY	_____	_____	_____	_____
0180	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	307,784.360 SY	_____	_____	_____	_____
0190	ATTD	515SX20-0001 FLEX.PAVE.EDGE PLANING MAINT	1,501.870 SY	_____	_____	_____	_____
0200	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	244,130.000 LF	_____	_____	_____	_____
0210	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	52,356.000 LF	_____	_____	_____	_____
0220	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	970.000 LF	_____	_____	_____	_____
0230	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	203.000 LF	_____	_____	_____	_____
0240	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	17.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM427PMB130210 Oversight/State Project No.: PM4B-964-27F, P401

Order No.: 412

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	704	704SD20-0050 DBL TURN ARR.THRU/LT OR RT TY B, CL I	3.000 EA	_____	_____	_____	_____
0260	704	704SD20-0092 MRKG INT'L ACCESSIBILITY SYMB TY B CL I	3.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	

SECTION: 0002

ALTERNATE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	
				Total Bid:		_____	