

Schedule of Items

Proposal ID: CM827LMB129824

Oversight/State Project No.: LM8B-968-27F, N501

Order No.: 802

Federal Project No.: PM08471

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	312SP20-0007 FLEXIBLE LATEX MODIFIED EMULSION TREATMENT, (TYPE B)	5,155.490 TON	_____	_____	_____	_____
0020	322	322SD20-0001 CRACK SEALANT/FILLER TYPE A	58,950.000 LB	_____	_____	_____	_____
0030	512	512SD20-0027 FLAGGER SERVICE	827.000 HR	_____	_____	_____	_____
0040	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	2,381.000 LF	_____	_____	_____	_____
0050	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	5,834.000 SF	_____	_____	_____	_____
0060	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	172,655.000 LF	_____	_____	_____	_____
0070	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	244,785.000 LF	_____	_____	_____	_____
0080	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	3,936.000 LF	_____	_____	_____	_____
0090	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	50.000 EA	_____	_____	_____	_____
0100	512	512SD20-0053 TEMP. PVMT. SYMB. MRKG R/R CROSSING TY. A	10.000 EA	_____	_____	_____	_____
0110	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT FOR UPC 129824	LUMP SUM	LUMP SUM		_____	_____
0120	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT FOR UPC 129827	LUMP SUM	LUMP SUM		_____	_____

Schedule of Items

Proposal ID: CM827LMB129824

Oversight/State Project No.: LM8B-968-27F, N501

Order No.: 802

Federal Project No.: PM08471

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	ATTD	512SX20-0006 TEMP. PVMT MRKG TEMP. DOUBLE TURN ARROW	4.000 EA	_____	_____	_____	_____
0140	ATTD	512SX20-0006 TEMP. PVMT MRKG TEMP. SCHOOL, TY. A - 10'	7.000 EA	_____	_____	_____	_____
0150	704	704SD20-0001 TYPE A PVMT LINE MRKG 4"	16,550.000 LF	_____	_____	_____	_____
0160	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	156,015.000 LF	_____	_____	_____	_____
0170	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	253,085.000 LF	_____	_____	_____	_____
0180	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	1,650.000 LF	_____	_____	_____	_____
0190	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	1,223.000 LF	_____	_____	_____	_____
0200	704	704SD20-0030 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 4"	1,025.000 LF	_____	_____	_____	_____
0210	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	1,300.000 LF	_____	_____	_____	_____
0220	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	1,000.000 EA	_____	_____	_____	_____
0230	704	704SD20-0042 PVMT MSG. MARK. R/R CROSSING TY. B, CL. II	5.000 EA	_____	_____	_____	_____
0240	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	25.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM827LMB129824

Oversight/State Project No.: LM8B-968-27F, N501

Order No.: 802

Federal Project No.: PM08471

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	704	704SD20-0051 DBL TURN ARR.THRU/LT OR RT TY B, CL II	2.000 EA	_____	_____	_____	_____
0260	704	704SD20-0124 PVMT MSG. MARK."SCHOOL" TY B, CL II, 10'	4.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____