

Schedule of Items

Proposal ID: C0000124092M01

Oversight/State Project No.: 0057-120-302, M501

Order No.: B38

Federal Project No.: STP-5120(126)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0029 SILTATION CONTROL EXCAVATION	229.000 CY				
0030	303	303SD20-0031 INLET PROTECTION TYPE B	12.000 EA				
0040	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,047.000 LF				
0050	305	305SD20-0011 AGGR. MATL. NO. 25 OR 26	23.000 TON				
0060	305	305SD20-0013 AGGR. MATL. NO. 3	1,194.000 TON				
0070	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	1,300.000 TON				
0080	315	315SD20-0005 ASPHALT CONCRETE TY. IM- 19.0D CONST	2,133.000 TON				
0090	315	315SD20-0008 ASPHALT CONCRETE TY. SM- 9.5D CONST	953.000 TON				
0100	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE (FULL DEPTH)	5,574.000 LF				
0110	316	316SD20-0030 CONCRETE ENTRANCE PAVE. 7"	96.000 SY				
0120	316	316SX20-0010 SAW-CUT HYDR.CEM.CONC.PAVE. (UNDERLYING HYDR. CEM. CONC. PAVE. 6.5 - 7.5 INCHES)	5,574.000 LF				

Schedule of Items

Proposal ID: C0000124092M01

Oversight/State Project No.: 0057-120-302, M501

Order No.: B38

Federal Project No.: STP-5120(126)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	502	502SD20-0011 CURB, STD. CG-2	377.000 LF	_____	_____	_____	_____
0140	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	249.000 LF	_____	_____	_____	_____
0150	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	186.000 LF	_____	_____	_____	_____
0160	502	502SD20-0053 MEDIAN STRIP MS-1	15.000 SY	_____	_____	_____	_____
0170	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	0.320 CY	_____	_____	_____	_____
0180	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	27.000 SY	_____	_____	_____	_____
0190	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	806.000 SY	_____	_____	_____	_____
0200	504	504SD20-0004 HYDR. CEMENT CONC. SIDEWALK 7"	49.000 SY	_____	_____	_____	_____
0210	507	507SD20-0005 FENCE FE-CL	57.000 LF	_____	_____	_____	_____
0220	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	5,254.000 SY	_____	_____	_____	_____
0230	510	510SD20-0038 ADJUST EXIST. VALVE & BOX	10.000 EA	_____	_____	_____	_____
0240	510	510SD20-0046 ADJUST EXIST. WATER METER & BOX	13.000 EA	_____	_____	_____	_____
0250	510	510SD20-0050 ADJUST EXIST FRAME & COVER	8.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124092M01

Oversight/State Project No.: 0057-120-302, M501

Order No.: B38

Federal Project No.: STP-5120(126)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	510	510SX20-0016 REMOVE EXIST. FENCE REMOVE EXIST. FENCE	57.000 LF	_____	_____	_____	_____
0270	511	511SD20-0001 ALLAYING DUST	120.000 HR	_____	_____	_____	_____
0280	512	512SD20-0013 TYPE 3 BARRICADE 8'	2.000 EA	_____	_____	_____	_____
0290	512	512SD20-0014 TEMPORARY SIGN	1,469.000 SF	_____	_____	_____	_____
0300	512	512SD20-0016 TEMPORARY CURB RAMP	1.000 EA	_____	_____	_____	_____
0310	512	512SD20-0018 PEDESTRIAN BARRICADE DEVICE	40.000 LF	_____	_____	_____	_____
0320	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	13,080.000 DAY	_____	_____	_____	_____
0330	512	512SD20-0027 FLAGGER SERVICE	2,520.000 HR	_____	_____	_____	_____
0340	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	7,492.000 LF	_____	_____	_____	_____
0350	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	24.000 EA	_____	_____	_____	_____
0360	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	14,331.000 LF	_____	_____	_____	_____
0370	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	103.000 LF	_____	_____	_____	_____
0380	512	512SD20-0065 TEMP. PVMT MRKG TY. D, CL. III, 24"	212.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124092M01

Oversight/State Project No.: 0057-120-302, M501

Order No.: B38

Federal Project No.: STP-5120(126)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	ATTD	512SX20-0019 TRAFFIC CONTROL TEMPORARY AUDIBLE INFORMATION DEVICE	2.000 EA	_____	_____	_____	_____
0400	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0410	514	514SD20-0001 FIELD OFFICE TY.I	6.000 MO	_____	_____	_____	_____
0420	515	515SD20-0005 FLEXIBLE PAVE. PLANING ABOVE 2"-4"	6,008.000 SY	_____	_____	_____	_____
0430	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
0440	602	602SD20-0006 TOPSOIL CLASS B	48.000 CY	_____	_____	_____	_____
0450	603	603SD20-0002 TEMPORARY SEED	18.000 LB	_____	_____	_____	_____
0460	603	603SD20-0003 REGULAR SEED	48.000 LB	_____	_____	_____	_____
0470	603	603SD20-0004 OVERSEEDING	39.000 LB	_____	_____	_____	_____
0480	603	603SD20-0005 LEGUME SEED	2.000 LB	_____	_____	_____	_____
0490	603	603SD20-0006 LEGUME OVERSEEDING	2.000 LB	_____	_____	_____	_____
0500	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,089.000 SY	_____	_____	_____	_____
0510	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	871.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124092M01

Oversight/State Project No.: 0057-120-302, M501

Order No.: B38

Federal Project No.: STP-5120(126)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	4.000 LF	_____	_____	_____	_____
0530	603	603SD20-0014 FERTILIZER NITROGEN - N	18.000 LB	_____	_____	_____	_____
0540	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	13.000 LB	_____	_____	_____	_____
0550	603	603SD20-0016 FERTILIZER POTASSIUM - K	13.000 LB	_____	_____	_____	_____
0560	603	603SD20-0017 LIME	0.990 TON	_____	_____	_____	_____
0570	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	2,503.000 SY	_____	_____	_____	_____
0580	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	14.000 EA	_____	_____	_____	_____
0590	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	4.000 EA	_____	_____	_____	_____
0600	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	108.000 LF	_____	_____	_____	_____
0610	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	24.000 LF	_____	_____	_____	_____
0620	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	11.000 EA	_____	_____	_____	_____
0630	701	701SD20-0001 SIGN PANEL	86.000 SF	_____	_____	_____	_____
0640	704	704SD20-0001 TYPE A PVMT LINE MRKG 4"	6,660.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124092M01

Oversight/State Project No.: 0057-120-302, M501

Order No.: B38

Federal Project No.: STP-5120(126)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	704	704SD20-0005 TYPE A PVMT LINE MRKG 24"	489.000 LF	_____	_____	_____	_____
0660	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	22.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____