Proposal ID: CM427PMF130192 **Oversight/State Project No.:** PM4F-964-27F, P401

Order No.: 416 **Federal Project No.:** PM04545

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	540.100 TON	_____	. _____	_____	. _____
0020	310	310SD20-0001 TACK COAT	26,405.760 GAL	_____	. _____	_____	. _____
0030	315	315SP20-0049 ASPH. CONC. BMD P+VO SM-9.5D	21,845.310 TON	_____	. _____	_____	. _____
0040	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0D	909.000 TON	_____	. _____	_____	. _____
0050	512	512SD20-0027 FLAGGER SERVICE	959.000 HR	_____	. _____	_____	. _____
0060	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	66,789.000 LF	_____	. _____	_____	. _____
0070	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	1,782.000 SF	_____	. _____	_____	. _____
0080	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	691,620.000 LF	_____	. _____	_____	. _____
0090	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	2,046.000 LF	_____	. _____	_____	. _____
0100	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM		_____	. _____
0110	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	2,317.600 SY	_____	. _____	_____	. _____
0120	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	219,792.650 SY	_____	. _____	_____	. _____

Proposal ID: CM427PMF130192 **Oversight/State Project No.:** PM4F-964-27F, P401

Order No.: 416 **Federal Project No.:** PM04545

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0130	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	333,785.000 LF	_____	_____	_____	_____
0140	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	11,830.000 LF	_____	_____	_____	_____
0150	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	1,083.000 LF	_____	_____	_____	_____
0160	704	704SD20-0044 PVMT SYMB MRKG THRU ARROW TY B, CL I	1.000 EA	_____	_____	_____	_____
0170	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	108.000 EA	_____	_____	_____	_____
0180	704	704SD20-0050 DBL TURN ARR.THRU/LT OR RT TY B, CL I	5.000 EA	_____	_____	_____	_____
0190	704	704SD20-0059 SYMB MRKG LANE REDUCTION ARR TY B CL I	2.000 EA	_____	_____	_____	_____
0200	704	704SD20-0128 SYMBOL MARKING BICYCLE TYPE B CLASS I	35.000 EA	_____	_____	_____	_____

Section: 0001 **Total:** _____

Proposal ID: CM427PMF130192 **Oversight/State Project No.:** PM4F-964-27F, P401

Order No.: 416 **Federal Project No.:** PM04545

Contractor: _____

SECTION: 0002 ALTERNATE BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0210	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	._____	_____	._____
		Section: 0002		**Total:**		_____	._____
				Total Bid:		**_____**	**._____**