Proposal ID: CM527PME129803 **Oversight/State Project No.:** PM5E-047-27F, P401

Order No.: 576 **Federal Project No.:** PM05554

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	243.000 TON				
0020	310	310SD20-0001 TACK COAT	34,499.260 GAL				
0030	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	25,196.000 LF				
0040	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	35,903.000 LF				
0050	315	315SP20-0048 ASPH. CONC. BMD P+VO SM-9.5A	10,064.110 TON				
0060	315	315SP20-0049 ASPH. CONC. BMD P+VO SM-9.5D	18,114.510 TON				
0070	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0D	660.000 TON				
0080	512	512SD20-0027 FLAGGER SERVICE	700.000 HR				
0090	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	371,968.000 LF				
0100	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	1,378.000 LF				
0110	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT	LUMP SUM	LUMP SUM			
0120	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	600.000 SY				

Proposal ID: CM527PME129803 **Oversight/State Project No.:** PM5E-047-27F, P401
Order No.: 576 **Federal Project No.:** PM05554

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0130	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	332,332.490 SY	_____	_____	_____	_____
0140	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	10,230.000 LF	_____	_____	_____	_____
0150	700	700SD20-0182 CONDUIT PVC 1"	510.000 LF	_____	_____	_____	_____
0160	702	702SD20-0002 FLEXIBLE POST DELINEATOR	8.000 EA	_____	_____	_____	_____
0170	703	703SD20-0042 LOOP SAW CUT 3/8"	2,860.000 LF	_____	_____	_____	_____
0180	703	703SD20-0043 LOOP SAW CUT 5/8"	680.000 LF	_____	_____	_____	_____
0190	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	58,120.000 LF	_____	_____	_____	_____
0200	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	129,386.000 LF	_____	_____	_____	_____
0210	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	2,911.000 LF	_____	_____	_____	_____
0220	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	2,269.000 LF	_____	_____	_____	_____
0230	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	42.000 EA	_____	_____	_____	_____
0240	704	704SD20-0035 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	2.000 EA	_____	_____	_____	_____

Proposal ID: CM527PME129803 **Oversight/State Project No.:** PM5E-047-27F, P401

Order No.: 576 **Federal Project No.:** PM05554

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0250	704	704SD20-0038 PVMT MSG. MARK. “SCHOOL” TY B, CL I, 6'	2.000 EA				
0260	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	63.000 EA				
0270	704	704SD20-0050 DBL TURN ARR.THRU/LT OR RT TY B, CL I	4.000 EA				
0280	704	704SD20-0095 SYMB MRKG BICYCLE THRU ARROW TY B CL I	28.000 EA				
		Section: 0001		**Total:**			

SECTION: 0002 ALTERNATE BID ITEM

Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0290	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIALS	1.000 TON				
		Section: 0002		**Total:**			
				Total Bid:			