Proposal ID: CM427PME130197 **Oversight/State Project No.:** PM4E-964-27S, P401
Order No.: 417 **Federal Project No.:** NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	1,624.270 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	35,270.200 GAL	_____	_____	_____	_____
0030	315	315SD20-0024 ASPH. CONC. TY. SM-9.0A MAINT	3,157.800 TON	_____	_____	_____	_____
0040	315	315SP20-0049 ASPH. CONC. BMD P+VO SM-9.5D	25,077.870 TON	_____	_____	_____	_____
0050	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0D	2,028.000 TON	_____	_____	_____	_____
0060	512	512SD20-0027 FLAGGER SERVICE	5,013.000 HR	_____	_____	_____	_____
0070	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	8,784.000 LF	_____	_____	_____	_____
0080	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	379.000 SF	_____	_____	_____	_____
0090	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	25,580.000 LF	_____	_____	_____	_____
0100	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	341.000 LF	_____	_____	_____	_____
0110	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM		_____	_____
0120	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	5,312.550 SY	_____	_____	_____	_____

Proposal ID: CM427PME130197 **Oversight/State Project No.:** PM4E-964-27S, P401
Order No.: 417 **Federal Project No.:** NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0130	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	13,801.260 SY	_____	_____	_____	_____
0140	ATTD	515SX20-0001 FLEX.PAVE.EDGE PLANING MAINT	33,484.350 SY	_____	_____	_____	_____
0150	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	13,260.000 LF	_____	_____	_____	_____
0160	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	447.000 LF	_____	_____	_____	_____
0170	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	15.000 EA	_____	_____	_____	_____
0180	704	704SD20-0050 DBL TURN ARR.THRU/LT OR RT TY B, CL I	2.000 EA	_____	_____	_____	_____

Section: 0001 **Total:** _____.____

SECTION: 0002 ALTERNATE BID ITEMS
Cat Alt Set ID: **Cat Alt Mbr ID:**

Proposal Line Number	Spec No.	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0190	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____

Section: 0002 **Total:** _____.____

Total Bid: _____.____